

STATUTORY ENGINEERING NOTICE: BlueprintIQ provides preliminary automated computer-vision analysis and quantity estimates. It does not replace a licensed architect, structural engineer, quantity surveyor, or local municipal authority approval. All quantities must be field-verified before material procurement.

1. PROJECT & DRAWING METADATA

Project Name	villa 1	Building Type	Residential
Floors	2	Unit System	METRIC
Target Area	180.0 m²	Soil Type	Not Provided
Drawing Scale	Unknown	Concrete Grade	M20
Wall Thickness	230 mm	Overall Confidence	LOW

2. CONSOLIDATED MATERIAL ESTIMATES (UNCERTAINTY-AWARE)

MATERIAL	ESTIMATED	RANGE	CONFIDENCE	CALCULATION BASIS
Cement (OPC/PPC 50kg Bags)	821.0 bags	755 - 903	MEDIUM	Concrete (557.4 bags) + Masonry (162.3 bags) ...
River Sand / M-Sand	81.5 m³	73 - 91	MEDIUM	Concrete (29.0m³) + Masonry (33.8m³) + Plaste...
Coarse Aggregate (20mm & 10mm Graded)	304.7 m³	55 - 67	MEDIUM	RCC Concrete (58.1m³) + PCC Bed (2.7m³)
Modular Clay / Fly Ash Bricks	47,190.0 nos	43,415 - 51,909	LOW	89.89 m³ net masonry x 500 bricks/m³ + 5% bre...
Reinforcement Steel (Fe500 TMT Rebar)	5,472.0 kg	4,396 - 6,464	MEDIUM	Slabs (3391.0 kg at 0.8% vol) + Beams/Columns...
Vitrified Floor Tiles (600x600mm)	61.8 m²	59 - 68	HIGH	Net floor area 57.2m² + 8% cutting and breaka...
Emulsion Paint & Primer (2 Coats)	148.4 litres	134 - 171	MEDIUM	Total plaster & ceiling area 1484.2m² / cover...

3. DETAILED BILL OF QUANTITIES (CIVIL & FINISHES)

CODE	DESCRIPTION	QTY	UNIT	RANGE	CONF.
CIV-01	Earthwork excavation in foundation trenches	43.46	m³	30.4 - 63.0	LOW
CIV-02	Plain Cement Concrete (PCC 1:4:8) in foundation bed (100mm)	3.15	m³	2.8 - 3.6	MEDIUM
CIV-03	Reinforced Cement Concrete (M20) for Slabs, Beams, Columns	69.12	m³	63.6 - 77.4	MEDIUM
CIV-04	Brick Masonry in Cement Mortar (1:6) with Modular Bricks	89.89	m³	80.9 - 98.9	LOW
CIV-05	Cement Plastering (12mm Internal 1:6 + 18mm External 1:4)	1124.16	m²	1045.5 - 1236.6	MEDIUM
CIV-06	Flooring with Vitrified Tiles including 8% wastage	61.78	m²	58.7 - 66.7	HIGH

4. DETECTED BLUEPRINT ANOMALIES & COMPLIANCE FINDINGS

ID	SEVERITY	FINDING & EVIDENCE	RECOMMENDED ACTION
ISSUE-001	HIGH	Drawing Scale Not Confirmed or Uncalibrated Drawing scale specified as 'Unknown' without dimension calibration points. <i>Ref: IS 1200 / ISO 128 Architectural Drawing Presentation Rules</i>	Perform scale calibration against a known reference dimension on the drawing before procurement. Verification: Required
ISSUE-002	MEDIUM	Staircase Riser and Tread Detail Missing on 2D Plan No textual riser/tread callouts (e.g. '18 Risers @ 165mm') identified in staircase zone. <i>Ref: IBC Section 1011.5.2 & NBC 4.8.1</i>	Request sectional drawing / stair detailing schedule for precise concrete and reinforcement calculation. Verification: Required

5. LOCAL AI (GEMMA 2B) SYNTHESIS & REASONING

Executive Synthesis: Preliminary architectural evaluation performed for Residential project. Detected 2 potential dimensional or compliance considerations (1 require urgent review). Soil parameter was 'Not Provided', requiring geotechnical confirmation before finalizing foundation estimates.

Uncertainty Assessment: Overall analysis confidence is rated as LOW. Confidence is constrained by 2D plan annotations and missing structural section schedules.

6. MISSING PARAMETERS & ENGINEERING ASSUMPTIONS

Missing Required / Recommended Inputs:

- **Soil Type:** Not Provided - *Foundation trench excavation, footing depth, and sub-base quantities cannot be verified without soil bearing capacity (SBC).*
- **Scale Calibration:** Uncalibrated - *Drawing scale relies on nominal text ratio ('1:100') rather than two-point physical dimension calibration. Coordinate errors may magnify calculated areas by 5-10%.*
- **Dimension Callout Annotations:** Incomplete Drawing Text - *Only 0 dimension strings extracted for 5 detected spaces. Several room polygons are inferred from wall boundaries.*

Applied Engineering Assumptions:

- Excavation depth assumed at nominal 1.2m for medium dense soil; footing sizes subject to soil report.
- Graphic scale ratio Unknown assumed uniformly proportional across X and Y axes.
- Reinforcement steel estimated via standard IS 456 thumb rules (0.8% for slabs, 1.5% for framed elements).
- Unannotated room dimensions derived from closed boundary polylines.